

Smith WWTF Force Main Phase B Mobile, AL



PROJECT OVERVIEW AND CHALLENGES

Bradshaw Construction installed 240 linear feet of 60 inch Permalok steel casing by microtunneling. The welded steel casing was installed on a 24/7 schedule in soft ground below the water table underneath a CSX railway. A 42 inch ductile iron carrier pipe was installed through the tunnel. Recovery of the MTBM within flowing ground adjacent to a truck route created additional complications that were overcome.



PROJECT INFORMATION - 526

OWNER:

City of Mobile
Board of Water & Sewer
Commissioners
(251) 342-5742

ENGINEER:

Volkert & Associates, Inc.
Bryan Peacock
(251) 342-1070

CONTRACTOR:

Hughes Plumbing & Utility
Contractors, Inc.

COMPLETION DATE:

2/27/2013

GEOLOGY:

Silty Sand

EXCAVATION METHOD:

Herrenknecht AVN-1200 MTBM

MINING DIMENSIONS:

240' x 60" Ø

FINAL LINING:

42" Ductile Iron Pipe

FOR MORE INFORMATION:

Eric Eisold, Vice President
410-970-8300
eeisold@bradshawcc.com
Refer to Project 526