

Arkendale-Powell's Creek Third Track Project Quantico, VA



## PROJECT OVERVIEW AND CHALLENGES

Bradshaw completed an emergency slipline repair project for KC Constructors (Kiewit-Clark JV). During the construction of a new track for CSX railroad, supportive steel sheeting was driven through an existing 60 inch RCP storm drain, requiring corrective measures. KC Constructors subcontracted Bradshaw to diagnose and repair the damage. After an initial exploration, 50 linear feet of 54 inch FRP was ordered and Bradshaw excavated a trench-box access shaft over the line directly downstream from the damaged joint and saw-cut an opening through the storm drain. The steel sheeting was cut and removed from inside of the storm drain, and the 50 linear feet of FRP was installed and grouted into place. All saw-cut work performed on the RCP for access was repaired, and the storm drain is back in full operation.





## **PROJECT INFORMATION - 564**

OWNER: CSX Transportation, Inc. 904-359-3200

ENGINEER: RK&K Engineers Michael Hogan 410-728-2900

CONTRACTOR: KC Constructors Joint Venture

COMPLETION DATE: 10/28/2016

GEOLOGY: N/A

EXCAVATION METHOD: Sliplining

MINING DIMENSIONS: 50' x 60"Ø

FINAL LINING: 54" Fiberglass Reinforced Concrete Pipe

## FOR MORE INFORMATION:

Jordan Bradshaw, Project Manager 410-970-8300 jordan.bradshaw@bradshawcc.com Refer to Project 564