

South County Re-Pump Station Water TM to 19th Ave. CIP 31969  
Ruskin, FL



## PROJECT OVERVIEW AND CHALLENGES

As part of Capital Improvement Project for Hillsborough County necessary to accommodate an expanding population, Bradshaw microtunnelled in a single drive 1,055 linear feet of 48" steel casing for 16" DIP carrier pipe under I-75. Bradshaw also installed a 16'x30' launch shaft and a 12'x16' receiving shaft. The depth of the shafts were approx. 25-feet deep and below the water table. Ground conditions were mostly sand. The main challenges for this project were double-shifting the tunneling operations per FDOT specifications, overhead power lines, a very tight schedule, and the length versus diameter of the tunnel making this Bradshaw's longest run for this diameter.



## PROJECT INFORMATION - 580

### OWNER:

Hillsborough County  
Public Utilities Dept. Water Resource  
Division  
813-272-5977  
HagwoodD@HCFLGov.net

### ENGINEER:

Black & Veatch Inc.  
Nicholas Wickhardt  
813-281-0032  
eckhardtnw@bv.com

### CONTRACTOR:

Westra Construction Corporation

### COMPLETION DATE:

11/20/2018

### GEOLOGY:

Sand

### EXCAVATION METHOD:

Herrenknecht AVN-800A MTBM

### MINING DIMENSIONS:

1055' x 48" Ø

### FINAL LINING:

16" Ductile Iron Pipe

### FOR MORE INFORMATION:

Mike Wanhatalo, Project Manager  
410-970-8300  
mwanhatalo@bradshawcc.com  
Refer to Project 580