

Sanitary Sewer Improvements; Goff Brook Overflow Closure Wethersfield, CT



PROJECT OVERVIEW AND CHALLENGES

Bradshaw completed a 60" microtunneling/conventional TBM project in Wethersfield, Connecticut for 30" and 48" CCFRPM sanitary sewer installations. The first tunnel (650') was installed by an Akkerman WM480 tunnel boring machine in stiff, wet clay. The 2nd (420'), 3rd (855'), 4th (152'), and 5th (450') tunnels were completed behind a Herrenknecht AVN 1200 microtunnel boring machine. An additional drive of 48" RCP was added to the project by change order to avoid a congested intersection and utility conflicts. This 510' drive was installed on an 1,168' radius curve. Ground conditions for microtunneling operations were predominantly siltstone, with occasional decomposed rock and dense alluvium. Major challenges for the project included installing the alignments on shallow slopes (.14%) with tight tolerances (+/- 1" on grade, no reverse flow), as well as limited construction footprints.



PROJECT INFORMATION - 572

OWNER:

Metropolitan District Commission
Jason Waterbury
860-278-7850
jwaterbury@themdc.com

ENGINEER:

Jacobs Engineering
John Ososkie
860-560-8906
john.ososkie@jacobs.com

CONTRACTOR:

Baltazar Contractors, Inc.

COMPLETION DATE:

5/9/2019

GEOLOGY:

Siltstone, Alluvium, & Decomposed
Rock

EXCAVATION METHOD:

Herrenknecht AVN-1200 MTBM

MINING DIMENSIONS:

311', 339' x 60" Ø

FINAL LINING:

48" Centrifugally Cast Fiberglass
Reinforced Pipe

FOR MORE INFORMATION:

Jordan Bradshaw, Project Manager
410-970-8300
jordan.bradshaw@bradshawcc.com
Refer to Project 572