

Cohas Brook Interceptor - Phase 1 Manchester, NH



PROJECT OVERVIEW AND CHALLENGES

As part of a microtunneling project Bradshaw installed two caissons: a 14' ID x 40' deep jacking shaft and a 10' ID x 60' deep receiving shaft. They were constructed using precast concrete segments and fitted with steel cutting shoes. They were sunk under their own weight, by excavating the soil with a crane & clam bucket. The lower portions were excavated subaqueous and the bottom slabs were tremie poured up to 7 feet thick to resist hydrostatic pressure. Both caissons were converted to permanent manholes once the microtunneling was complete. The principal challenges were 1) transporting the large and heavy precast concrete segments from the manufacturing plant to the site, 2) stopping the 14' ID jacking shaft in the extremely soft silt soils at the proper elevation, and 3) dealing with boulders above the final invert of the 10' receiving shaft.





PROJECT INFORMATION - 324

OWNER:

City of Manchester 475 Valley Street Manchester, NH 03103 (603) 624-6444

ENGINEER: Costello, Lomasney & deNapoli, Inc. Leslie G. Nelson, P.E. (603) 668-8223

CONTRACTOR: Park Construction Corp.

COMPLETION DATE: 7/15/1999

GEOLOGY: Glacial Deposits of Silt, Sand, Cobbles & Boulders

EXCAVATION METHOD: Crane & Clam Bucket

MINING DIMENSIONS: 10' x 60VF & 14' x 40VF

FINAL LINING: Precast Segments

FOR MORE INFORMATION:

Lester Bradshaw, Jr., President (410) 970-8300 lester.bradshaw@bradshawcc.com Refer to Project 324